

BLACK AND VEATCH KANSAS CITY MO

NATIONAL DAM SAFETY PROGRAM. DREXEL LAKE DAM (MO 20046), OSAGE --ETC(U)

APR 79 P R ZAMAN, L K LAMPE, H L CALLAHAN

DACW43-79-C-0040

NL

1.  $\mathbb{C}P^1$

END  
DATE  
FILMED  
11-81  
DTIC

**OSAGE-GASCONADE BASIN**

①

**AD A106300**

**LEVEL II**

**DREXEL LAKE DAM**

**BATES COUNTY, MISSOURI**

**MO 20046**

**PHASE 1 INSPECTION REPORT  
NATIONAL DAM SAFETY INSPECTION**

**FILE COPY**



**United States Army  
Corps of Engineers**  
... Serving the Army  
... Serving the Nation

**St. Louis District**

**DTIC  
ELECT  
OCT 28 1981  
E**

**PREPARED BY: U.S. ARMY ENGINEER DISTRICT, ST. LOUIS**

**FOR: STATE OF MISSOURI**

**APRIL 1979**

This document has been approved  
for public release and sale; its  
distribution is unlimited.

**81 10 26 082**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A106 300	
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Drexel Lake Dam (MO 20046) Bates County, Missouri		5. TYPE OF REPORT & PERIOD COVERED Final Report
6. AUTHOR(s) Black & Veatch, Consulting Engineers		7. PERFORMING ORG. REPORT NUMBER
8. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		9. CONTRACT OR GRANT NUMBER(s) DACW43-79-C-0040
10. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		11. REPORT DATE April 1979
12. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		13. NUMBER OF PAGES Approximately 40
		14. SECURITY CLASS. (of this report) UNCLASSIFIED
15. DISTRIBUTION STATEMENT (of this Report) Approved for release; distribution unlimited.		16. DECLASSIFICATION/DOWNGRADING SCHEDULE
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) National Dam Safety Program. Drexel Lake Dam (MO 20046), Osage - Gasconade Basin, Bates County, Missouri. Phase I Inspection Report.		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		

DD FORM 1 JAN 78 1073

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

## INSTRUCTIONS FOR PREPARATION OF REPORT DOCUMENTATION PAGE

**RESPONSIBILITY.** The controlling DoD office will be responsible for completion of the Report Documentation Page, DD Form 1473, in all technical reports prepared by or for DoD organizations.

**CLASSIFICATION.** Since this Report Documentation Page, DD Form 1473, is used in preparing announcements, bibliographies, and data banks, it should be unclassified if possible. If a classification is required, identify the classified items on the page by the appropriate symbol.

### COMPLETION GUIDE

**General.** Make Blocks 1, 4, 5, 6, 7, 11, 13, 15, and 16 agree with the corresponding information on the report cover. Leave Blocks 2 and 3 blank.

**Block 1.** Report Number. Enter the unique alphanumeric report number shown on the cover.

**Block 2.** Government Accession No. Leave Blank. This space is for use by the Defense Documentation Center.

**Block 3.** Recipient's Catalog Number. Leave blank. This space is for the use of the report recipient to assist in future retrieval of the document.

**Block 4.** Title and Subtitle. Enter the title in all capital letters exactly as it appears on the publication. Titles should be unclassified whenever possible. Write out the English equivalent for Greek letters and mathematical symbols in the title (see "Abstracting Scientific and Technical Reports of Defense-sponsored RDT/E," AD-667 000). If the report has a subtitle, this subtitle should follow the main title, be separated by a comma or semicolon if appropriate, and be initially capitalized. If a publication has a title in a foreign language, translate the title into English and follow the English translation with the title in the original language. Make every effort to simplify the title before publication.

**Block 5.** Type of Report and Period Covered. Indicate here whether report is interim, final, etc., and, if applicable, inclusive dates of period covered, such as the life of a contract covered in a final contractor report.

**Block 6.** Performing Organization Report Number. Only numbers other than the official report number shown in Block 1, such as series numbers for in-house reports or a contractor/grantee number assigned by him, will be placed in this space. If no such numbers are used, leave this space blank.

**Block 7.** Author(s). Include corresponding information from the report cover. Give the name(s) of the author(s) in conventional order (for example, John R. Doe or, if author prefers, J. Robert Doe). In addition, list the affiliation of an author if it differs from that of the performing organization.

**Block 8.** Contract or Grant Number(s). For a contractor or grantee report, enter the complete contract or grant number(s) under which the work reported was accomplished. Leave blank in in-house reports.

**Block 9.** Performing Organization Name and Address. For in-house reports enter the name and address, including office symbol, of performing activity. For contractor or grantee reports enter the name and address of the contractor or grantee who prepared the report, and identify the appropriate corporate division, school, laboratory, etc., of the author. List city, state, and ZIP Code.

**Block 10.** Program Element, Project, Task Area, and Work Unit Numbers. Enter here the number code from the applicable Department of Defense form, such as the DD Form 1498, "Research and Technology Work Unit Summary" or the DD Form 1634, "Research and Development Planning Summary," which identifies the program element, project, task area, and work unit or equivalent under which the work was authorized.

**Block 11.** Controlling Office Name and Address. Enter the full, official name and address, including office symbol, of the controlling office. (Equates to funding/sponsoring agency. For definition see DoD Directive 5200.20, "Distribution Statements on Technical Documents.")

**Block 12.** Report Date. Enter here the day, month, and year or month and year as shown on the cover.

**Block 13.** Number of Pages. Enter the total number of pages.

**Block 14.** Monitoring Agency Name and Address (if different from Controlling Office). For use when the controlling or funding office does not directly administer a project, contract, or grant, but delegates the administrative responsibility to another organization.

**Blocks 15 & 15a.** Security Classification of the Report: Declassification/Downgrading Schedule of the Report. Enter in 15 the highest classification of the report. If appropriate, enter in 15a the declassification/downgrading schedule of the report, using the abbreviations for declassification/downgrading schedules listed in paragraph 4-207 of DoD 5200.1-R.

**Block 16.** Distribution Statement of the Report. Insert here the applicable distribution statement of the report from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

**Block 17.** Distribution Statement (of the abstract entered in Block 20, if different from the distribution statement of the report). Insert here the applicable distribution statement of the abstract from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

**Block 18.** Supplementary Notes. Enter information not included elsewhere but useful, such as: Prepared in cooperation with ... Translation of (or by) ... Presented at conference of ... To be published in ...

**Block 19.** Key Words. Select terms or short phrases that identify the principal subjects covered in the report, and are sufficiently specific and precise to be used as index entries for cataloging, conforming to standard terminology. The DoD "Thesaurus of Engineering and Scientific Terms" (TEST), AD-672 000, can be helpful.

**Block 20.** Abstract. The abstract should be a brief (not to exceed 200 words) factual summary of the most significant information contained in the report. If possible, the abstract of a classified report should be unclassified and the abstract to an unclassified report should consist of publicly-releasable information. If the report contains a significant bibliography or literature survey, mention it here. For information on preparing abstracts see "Abstracting Scientific and Technical Reports of Defense-Sponsored RDT&E," AD-667 000.

# **OSAGE-GASCONADE BASIN**

**DREXEL LAKE DAM**

**BATES COUNTY, MISSOURI**

**MO 20046**

## **PHASE 1 INSPECTION REPORT NATIONAL DAM SAFETY INSPECTION**



**United States Army  
Corps of Engineers**

*... Serving the Army  
... Serving the Nation*

**St. Louis District**

**PREPARED BY: U.S. ARMY ENGINEER DISTRICT, ST. LOUIS**

**FOR: STATE OF MISSOURI**

**APRIL 1979**

DREXEL LAKE DAM  
BATES COUNTY, MISSOURI

MISSOURI INVENTORY NO. 20046

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

PREPARED BY:  
BLACK & VEATCH  
CONSULTING ENGINEERS  
KANSAS CITY, MISSOURI

Accession For	
FTIS CRAGI	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A	

UNDER DIRECTION OF  
ST. LOUIS DISTRICT CORPS OF ENGINEERS  
FOR  
GOVERNOR OF MISSOURI

APRIL 1979



DEPARTMENT OF THE ARMY  
ST. LOUIS DISTRICT, CORPS OF ENGINEERS  
210 NORTH 12TH STREET  
ST. LOUIS, MISSOURI 63101

IN REPLY REFER TO

SUBJECT: Drexel Lake Dam Phase I Inspection Report

This report presents the results of field inspection and evaluation of the Drexel Lake Dam:

It was prepared under the National Program of Inspection of Non-Federal Dams.

This dam has been classified as unsafe, non-emergency by the St. Louis District as a result of the application of the following criteria:

- 1) Spillway will not pass 50 percent of the Probable Maximum Flood
- 2) Overtopping could result in dam failure
- 3) Dam failure significantly increases the hazard to loss of life downstream

**SIGNED**

SUBMITTED BY: \_\_\_\_\_  
Chief, Engineering Division

**SIGNED**

APPROVED BY: \_\_\_\_\_  
Colonel, CE, District Engineer

**30 JUL 1979**

\_\_\_\_\_  
Date

**30 JUL 1979**

\_\_\_\_\_  
Date



## PHASE I REPORT

### NATIONAL DAM SAFETY PROGRAM


Name of Dam	Drexel Lake Dam
State Located	Missouri
County Located	Bates County
Stream	North Sugar Creek
Date of Inspection	5 April 1979


Drexel Lake Dam was inspected by a team of engineers from Black & Veatch, Consulting Engineers for the St. Louis District, Corps of Engineers. The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.


The guidelines used in the assessment were furnished by the Department of the Army, Office of the Chief of Engineers and developed with the help of several Federal and state agencies, professional engineering organizations, and private engineers. Based on these guidelines, this dam is classified as a small size dam with a high downstream hazard potential. According to the St. Louis District, Corps of Engineers failure would threaten the life and property of approximately four families and would potentially cause appreciable damage to the water treatment plant for the City of Drexel within the estimated damage zone which extends 0.5 miles downstream of the dam.

Our inspection and evaluation indicates the spillway does not meet the criteria set forth in the guidelines for a dam having the above size and hazard potential. The spillway will not pass the probable maximum flood without overtopping but will pass 20 percent of the probable maximum flood, which is greater than the calculated 100-year flood. The spillway design flood recommended by the guidelines is 50 to 100 percent of the probable maximum flood. Considering the size of the dam and reservoir and the downstream hazard potential, the appropriate spillway design capacity for this dam should be 50 percent of the probable maximum flood. The probable maximum flood is defined as the flood discharge that may be expected from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region.

There were no observed deficiencies or conditions existing at the time of the inspection which indicated an immediate safety hazard. Seepage and stability analyses required by the guidelines were not available. Detailed seepage and stability analyses of the existing dam, as required by the guidelines, should be performed. A detailed report on the dam is attached.

  
Paul R. Zaman, PE  
Illinois 62-29261

  
Les K. Lampe, PE  
Kansas 7407

  
Harry L. Callahan, Partner  
Black & Veatch



OVERVIEW OF LAKE AND DAM

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
DREXEL LAKE DAM

TABLE OF CONTENTS

<u>Paragraph No.</u>	<u>Title</u>	<u>Page No.</u>
SECTION 1 - PROJECT INFORMATION		
1.1	General	1
1.2	Description of Project	1
1.3	Pertinent Data	2
SECTION 2 - ENGINEERING DATA		
2.1	Design	5
2.2	Construction	5
2.3	Operation	5
2.4	Evaluation	5
2.5	Geology	5
SECTION 3 - VISUAL INSPECTION		
3.1	Findings	6
3.2	Evaluation	6
SECTION 4 - OPERATIONAL PROCEDURES		
4.1	Procedures	7
4.2	Maintenance of Dam	7
4.3	Maintenance of Operating Facilities	7
4.4	Description of Any Warning System in Effect	7
4.5	Evaluation	7
SECTION 5 - HYDRAULIC/HYDROLOGIC		
5.1	Evaluation of Features	8
SECTION 6 - STRUCTURAL STABILITY		
6.1	Evaluation of Structural Stability	10
SECTION 7 - ASSESSMENT/REMEDIAL MEASURES		
7.1	Dam Assessment	11
7.2	Remedial Measures	11

TABLE OF CONTENTS (Cont'd)

LIST OF PLATES

<u>Plate No.</u>	<u>Title</u>
1	Location Map
2	Vicinity Topography
3	Plan
4	Section
5	Spillway Sections
6	Photo Index

LIST OF PHOTOGRAPHS

<u>Photo No.</u>	<u>Title</u>
1	View of Lake from Dam
2	Upstream Face of Dam Looking South
3	Crest of Dam Looking South
4	Downstream Face of Dam Looking South
5	Intake Structure and Inflow Pipe
6	Spillway Crest
7	South Dam Abutment and Spillway Discharge Channel
8	Spillway Discharge Channel Looking Upstream
9	Spillway Discharge Channel Looking Downstream
10	Damage Zone Looking Downstream from the Dam

APPENDIX

Appendix A - Hydrologic Computations

## SECTION 1 - PROJECT INFORMATION

### 1.1 GENERAL

a. Authority. The National Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of safety inspection of dams throughout the United States. Pursuant to the above, the District Engineer of the St. Louis District, Corps of Engineers, directed that a safety inspection of the Drexel Lake Dam be made.

b. Purpose of Inspection. The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.

c. Evaluation Criteria. Criteria used to evaluate the dam were furnished by the Department of the Army, Office of the Chief of Engineers, in "Recommended Guidelines for Safety Inspection of Dams". These guidelines were developed with the help of several Federal agencies and many State agencies, professional engineering organizations, and private engineers.

### 1.2 DESCRIPTION OF PROJECT

#### a. Description of Dam and Appurtenances.

(1) Drexel Dam is an earth structure located on North Sugar Creek in northwestern Bates County, Missouri (Plate 1). The dam is 460 feet long and forms a 26-acre water supply and fishing lake. The structure is well maintained with rock riprap on both the upstream and downstream faces. The spillway is located at the left abutment, and the water intake to the treatment plant is near the middle of the dam. The watershed is primarily comprised of crop and grass land. Topography of the contributing watershed is characterized by flat lands to gently rolling hills. Topography in the vicinity of the dam is shown on Plate 2.

(2) The spillway is located at the left abutment of the dam. It consists of a concrete overflow weir, a concrete wall along the left abutment of the dam, and a discharge channel consisting of natural earth, broken shale, and limestone. The side slopes of the channel are moderately tree covered.

(3) An intake structure for the water treatment plant is located in the dam about 130 feet north of the south abutment. The structure is a square concrete tower with multilevel inlets. Reportedly a 3-inch diameter pipe goes from the intake structure, through the dam, to the water treatment plant located near the downstream face at the north end of the dam.

(4) Water is pumped into Drexel Lake from another lake located approximately 3/4 mile south of the dam. The 6-inch diameter inflow pipe is located approximately 150 feet north of the south abutment.

(5) Pertinent physical data are given in paragraph 1.3.

b. Location. The dam is located in northwestern Bates County, Missouri, as indicated on Plate 1. The lake formed by the dam is shown on the United States Geological Survey 7.5 minute series quadrangle map for Drexel, Missouri, in Section 6 of T42N, R33W.

c. Size Classification. Criteria for determining the size classification of dams and impoundments are presented in the guidelines referenced in paragraph 1.1c above. Based on these criteria, the dam and impoundment are in the small size category.

d. Hazard Classification. The hazard classification assigned by the Corps of Engineers for this dam is as follows: The Drexel Lake Dam has a high hazard potential, meaning that the dam is located where failure may cause loss of life, and serious damage to homes, agricultural, industrial and commercial facilities, and to important public utilities, main highways, or railroads. For the Drexel Lake Dam the flood damage zone extends downstream for 0.5 mile. Within the damage zone are four homes and the water treatment plant for the City of Drexel.

e. Ownership. The dam is owned by the City of Drexel. Information can be obtained from City Hall, Drexel, Missouri 64742.

f. Purpose of Dam. The dam forms a 26-acre lake for water supply and fishing.

g. Design and Construction History. Data relating to the design and construction were not available. The dam was built in 1953.

h. Normal Operating Procedure. Normal rainfall, runoff, transpiration, evaporation, withdrawals to the water treatment plant, and outflow through the spillway all combine to maintain a relatively stable water surface elevation. During periods of little or no rainfall and heavy water usage, water is pumped into Drexel Lake from a lake located south of Drexel to maintain the pool level for water supply and recreational uses.

### 1.3 PERTINENT DATA

a. Drainage Area - 2,920 acres

b. Discharge at Damsite.

(1) Normal discharge at the damsite is through an uncontrolled spillway.

(2) Estimated experienced maximum flood at damsite - Unknown.

(3) Estimated ungated spillway capacity at maximum pool elevation 3,480 cfs (top of dam El. 972.8).

c. Elevation (Feet Above M.S.L.).

(1) Top of dam - 972.8 ± (see Plate 3)

(2) Spillway crest - 965.0

(3) Streambed at toe of dam - 950.0 ±

(4) Maximum tailwater - Unknown.

d. Reservoir.

(1) Length of maximum pool - 4,700 feet ±

(2) Length of normal pool - 3,200 feet ±

e. Storage (Acre-feet).

(1) Top of dam - 502

(2) Spillway crest - 112 (from 1974 inventory)

(3) Design surcharge - Not available.

f. Reservoir Surface (Acres).

(1) Top of dam - 88

(2) Spillway crest - 26

g. Dam.

(1) Type - Earth embankment

(2) Length - 460 feet

(3) Height - 17 feet ±

(4) Top width - 9 feet



(5) Side slopes - upstream face 1.0 V to 2.5 H, downstream face 1.0 V to 2.8 H (see Plate 4)

(6) Zoning - Unknown.

(7) Impervious core - Unknown.

(8) Cutoff - Unknown.

(9) Grout curtain - Unknown.

h. Diversion and Regulating Tunnel - None.

i. Spillway.

(1) Type - Concrete weir with natural earth, shale, and limestone channel.

(2) Width of channel - 50 to 60 feet, varies.

(3) Crest elevation - 965.0 feet m.s.l.

(4) Gates - None.

(5) Upstream channel - Not applicable.

(6) Downstream channel - Open channel comprised of natural earth, broken limestone, and shale located on the left end of the embankment.

j. Regulating Outlets - The intake structure and 3-inch diameter pipe to the treatment plant could be used to drawdown the lake. The small diameter of the pipe would necessitate a long drawdown time.

## SECTION 2 - ENGINEERING DATA

### 2.1 DESIGN

Design data were unavailable.

### 2.2 CONSTRUCTION

Construction records were unavailable, however, the owners stated that the dam was built in 1953.

### 2.3 OPERATION

The maximum recorded loading on the dam is unknown.

### 2.4 EVALUATION

- a. Availability. No engineering data could be obtained.
- b. Adequacy. No engineering data were available upon which to make a detailed assessment of the design, construction, and operation. Detailed seepage and stability analyses should be performed as required by the guidelines.
- c. Validity. The validity of the design, construction, and operation could not be determined due to the lack of engineering data.

### 2.5 GEOLOGY

The dam is located in a valley formed in limestones and shales of the Pennsylvanian System, Marmaton Group. These are overlain by the Summit Silt Loam soil series, a residual clayey silt and silty clay soil varying in thickness from 0 to 5 feet. The foundation and abutments of the dam are anticipated to be shale and limestone overlain by silty clay. Limestone and shale are exposed in the spillway channel and downstream channel below the spillway. The bedding is horizontal and thin with closed bedding planes and a few widely spaced, closed, vertical joints.

### SECTION 3 - VISUAL INSPECTION

#### 3.1 FINDINGS

a. General. A visual inspection of Drexel Lake Dam was made on 5 April 1979. The inspection team included professional engineers with experience in dam design and construction, hydrologic - hydraulic engineering, and geotechnical engineering. Specific observations are discussed below. No observations were made of the condition of the upstream face of the dam below the pool elevation at the time of the inspection.

b. Dam. The inspection team observed the following items at the dam. There was no observable erosion of either the upstream or downstream slope of the embankment. The limestone riprap on both slopes is in good condition. The dam is well maintained. Brush is regularly removed from the embankment and the grass cover beyond the riprap on the downstream slope of the embankment is mowed regularly. No sloughing or seepage was observed on the downstream embankment. No settlement of the embankment was noticed, nor were any significant animal burrows present in the embankment.

c. Appurtenant Structures. The inspection team observed the following items pertaining to appurtenant structures. The spillway constructed at the left abutment of the embankment appears to be in good condition. The spillway has a concrete sill at the upstream end which serves as a broad-crested weir. The base of the spillway is unlined and is broken shale and limestone. The right wall of the spillway is a concrete wall 5 feet high, extending approximately 80 feet along the right side of the spillway discharge channel. The left side of the spillway channel is natural earth, broken shale, and limestone, with a moderate cover of brush and small trees. Minor erosion of the bottom and left side of the spillway channel has occurred.

d. Reservoir Area. No slides or excessive erosion due to wave action were observed along the shore of the reservoir. A minor amount of siltation has occurred at the upstream end of the reservoir.

e. Downstream Channel. Open channel comprised of broken limestone and shale located at the left end of the dam embankment.

#### 3.2 EVALUATION

None of the conditions observed are significant enough to indicate a need for immediate remedial action. The inspection team observed no deficiencies at the dam at the time of the inspection.

## SECTION 4 - OPERATIONAL PROCEDURES

### 4.1 PROCEDURES

The pool is primarily controlled by rainfall, runoff, evaporation, withdrawals to the water treatment plant, and capacity of the uncontrolled spillway. During periods of little or no rain and heavy water usage, water is pumped into Drexel Lake in a 6-inch cast iron pipe from a lake located approximately 3/4 mile south of the dam. Water is withdrawn from Drexel Lake by a 3-inch pipe which connects to the treatment plant near the downstream face of the dam.

### 4.2 MAINTENANCE OF DAM

Trees and brush are regularly removed from the embankment. Grass on or near the embankment is cut periodically as necessary.

### 4.3 MAINTENANCE OF OPERATING FACILITIES

Maintenance of the inflow pipe and the withdrawal pipe is performed as needed for water supply operations.

### 4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

The inspection team is not aware of any existing warning system for this dam.

### 4.5 EVALUATION

At the time of the inspection no deficiencies were observed. The dam appears to be in good condition and well maintained.

## SECTION 5 - HYDRAULIC/HYDROLOGIC

### 5.1 EVALUATION OF FEATURES

a. Design Data. Design data pertaining to hydrology and hydraulics were unavailable.

b. Experience Data. The drainage area and lake surface area are developed from USGS Drexel and Freeman Quadrangle Maps. The spillway and dam layouts are from surveys made during the inspection. The soils of the watershed consist of the Summit Silt Loam soil series. This soil is an upland residual soil developed from weathering of shales and thin limestones of Pennsylvanian age. The soil consists of a mixture of sand, silt, clay, and organic matter. The near-surface soil is predominantly clayey silt; the deeper soil is predominantly silty clay. For engineering purposes, the near surface soil is classified ML-CL, and the deeper soil is classified as CL. The lower permeability of the deeper soil may cause increased runoff during long periods of high precipitation. Soils are generally thicker on the uplands and in the valleys and thinner on valley slopes.

c. Visual Observations.

- (1) The spillway is in good condition.
- (2) The intake structure and 3-inch line to the water treatment plant could be used to drawdown the pool. Because of the minor capacity of the pipeline, drawdown of the pool would require a considerably long time.
- (3) A spillway and exit channel are located near the left abutment. Spillway discharges are not anticipated to endanger the integrity of the dam.

d. Overtopping Potential. The spillway will not pass the probable maximum flood without overtopping the dam. The probable maximum flood is defined as the flood discharge that may be expected from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region. The spillway will pass 20 percent of the probable maximum flood without overtopping the dam. This flood is greater than the 100-year flood. The distribution for the 100-year frequency rainfall was supplied by the St. Louis District, Corps of Engineers. According to the recommended guidelines from the Department of the Army, Office of the Chief of Engineers, a high hazard dam of small size should pass 50 to 100 percent of the probable maximum flood. Based on the amount of water impounded by the dam and the hazard classification, the spillway should be designed to pass 50 percent of the maximum probable flood. The portion of the estimated peak discharge

of the probable maximum flood overtopping the dam would be 14,650 cfs of the total discharge from the reservoir of 22,960 cfs. The estimated duration of overtopping is 6.7 hours with a maximum height of 4.6 feet. The portion of the estimated peak discharge of 50 percent of the probable maximum flood overtopping the dam would be 5,520 cfs of the total discharge of the reservoir of 10,530 cfs with a maximum depth over the dam of 2.4 feet. The estimated duration of overtopping is 4.3 hours. The riprap on the upstream and downstream slopes of the dam will provide protection from erosion during overtopping. Failure of upstream water impoundments shown on the 1975 revised USGS map would not have a significant impact on the hydrologic or hydraulic analysis.

According to the St. Louis District, Corps of Engineers, the effect from rupture of the dam could extend approximately 0.5 mile downstream of the dam. There are four dwellings and the water treatment plant for the City of Drexel which could be severely damaged and lives could be lost should failure of the dam occur.

## SECTION 6 - STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations. Visual observations of conditions which affect the structural stability of this dam are discussed in Section 3, paragraph 3.1b.

b. Design and Construction Data. No design data relating to the structural stability of the dam were found. Detailed seepage and stability analysis should be performed as required by the guidelines.

c. Operating Records. No operational records exist.

d. Post Construction Changes. No known post construction changes.

e. Seismic Stability. The dam is located in Seismic Zone 1 which is a zone of minor seismic risk. A properly designed and constructed earth dam using sound engineering principles and conservatism should pose no serious stability problems during earthquakes in this zone.

The seismic stability of an earth dam is dependent upon a number of factors: The important factors being embankment and foundation material classification and shear strengths; abutment materials, conditions, and strength; embankment zoning; and embankment geometry. Adequate descriptions of embankment design parameters, foundation and abutment conditions, or static stability analyses to assess the seismic stability of this embankment were not available and therefore no inferences will be made regarding the seismic stability. An assessment of the seismic stability should be included as part of the stability analysis required by the guidelines.

## SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

### 7.1 DAM ASSESSMENT

a. Safety. No deficiencies were observed by the inspection team during the visual inspection.

b. Adequacy of Information. Due to the lack of engineering design data, the conclusions in this report were based only on performance history and visual conditions. The inspection team considers that these data are sufficient to support the conclusions herein. However, seepage and stability analyses are needed to satisfy the requirements of the guidelines.

c. Urgency. It is the opinion of the inspection team that a program should be developed to implement measures recommended in paragraph 7.2b.

d. Necessity for Phase II. The Phase I investigation does not raise any serious questions relating to the safety of the dam or identify any serious dangers that would require a Phase II investigation.

e. Seismic Stability. This dam is located in Seismic Zone 1. Adequate description of embankment design parameters, foundation and abutment conditions, or static stability analyses to assess the seismic stability of this embankment was not available and therefore no inferences will be made regarding the seismic stability. An assessment of the seismic stability should be included as part of the recommended stability analysis.

### 7.2 REMEDIAL MEASURES

a. Alternatives. The present spillway has the capacity to pass 20 percent of the probable maximum flood without overtopping the dam. In order to pass 50 percent of the probable maximum flood as required by the Recommended Guidelines, the spillway size and/or height of dam would need to be increased.

b. O&M Maintenance and Procedures. The following O&M maintenance and procedures are recommended:


(1) Check the downstream face of the dam periodically for seepage and stability problems. If seepage flows are observed or sloughing on the downstream embankment slope is noted, the dam should immediately be inspected and the condition evaluated by an engineer experienced in design and construction of earthen dams.





(2) The present regular maintenance program should be continued to control the growth of brush and grass on the dam embankment.

(3) Seepage and stability analysis should be performed by a professional engineer experienced in the design and construction of dams to satisfy the requirements of the guidelines.

(4) A detailed inspection of the dam should be made periodically by an engineer experienced in design and construction of dams. More frequent inspections may be required if deficiencies are observed.







WATER  
TREATMENT  
PLANT

TOE OF SLOPE

2+00  
EL 9729

3+00  
EL 9728

4+00  
EL 973.1

4+60  
EL 971.5

5+50  
EL 973.5

CL DAM

CIP INFLOW PIPE

WATER TREATMENT PLANT  
STRUCTURE


CL ROAD

LAKE




DREXEL LAKE  
PLAN


12



DREXEL LAKE  
TYPICAL SECTION

DREXEL LAKE  
TYPICAL SECTION










WATER  
TREATMENT  
PLANT

OF SLOPE



LEGEND

← ① PHOTO LOCATION AND  
DIRECTION



DREXEL LAKE  
PHOTO INDEX



PHOTO 1: VIEW OF LAKE FROM DAM



PHOTO 2: UPSTREAM FACE OF DAM LOOKING SOUTH



PHOTO 3: CREST OF DAM LOOKING SOUTH



PHOTO 4: DOWNSTREAM FACE OF DAM LOOKING SOUTH



PHOTO 5: INTAKE STRUCTURE AND INFLOW PIPE



PHOTO 6: SPILLWAY CREST



PHOTO 7: SOUTH DAM ABUTMENT AND SPILLWAY DISCHARGE CHANNEL



PHOTO 8: SPILLWAY DISCHARGE CHANNEL LOOKING UPSTREAM



PHOTO 9: SPILLWAY DISCHARGE CHANNEL LOOKING DOWNSTREAM



PHOTO 10: DAMAGE ZONE LOOKING DOWNSTREAM FROM DAM

APPENDIX A  
HYDROLOGIC COMPUTATIONS

## HYDROLOGIC COMPUTATIONS

1. The Soil Conservation Service (SCS) dimensionless unit hydrograph and HEC-1 (1) were used to develop the inflow hydrographs, and hydrologic inputs are as follows:

a. Twenty-four hour, probable maximum precipitation determined from U.S. Weather Bureau Hydrometeorological Report No. 33.

200 square mile, 24 hour rainfall inches	- 25.1
10 square mile, 6 hour percent of 24 hour 200 square mile rainfall	- 101%
10 square mile, 12 hour percent of 24 hour 200 square mile rainfall	- 120%
10 square mile, 24 hour percent of 24 hour 200 square mile, rainfall	- 130%
10 square miles, 48 hour percent of 24 hour 200 square mile, rainfall	- 140%

b. Drainage area = 2,920 acres.

c. Time of concentration:  $T_c = (11.9 \times L^3/H)^{0.385} = 1.37 \text{ hours} = 83 \text{ minutes}$  (L = length of longest watercourse in miles, H = elevation difference in feet) (2)

d. Losses were determined in accordance with SCS methods for determining runoff using a curve number of 89 and antecedent moisture condition III. The hydrologic soil group in the basin was type C.

2. Spillway release rates are based on the broad-crested weir equation.

Broad-crested weir equation:

$$Q = CLH^{1.5} \text{ (for concrete section, } C = 2.64 \text{ to } 2.68, \\ L = 24.0 \text{ feet; for grass section } C = 2.63, L = 26 \text{ to } 46 \text{ feet; } H \text{ is the head on weir).}$$

Discharge rates over the top of the dam are also based on the broad-crested weir equation:

$$Q = CLH^{1.5} \text{ (} C = 2.7, L = 460 \text{ feet).}$$



3. The elevation-storage relationship above normal pool elevation was constructed by planimetering the area enclosed within each contour above normal pool. The storage between two elevations was computed by multiplying the average of the areas at the two elevations by the elevation difference. The summation of these increments below a given elevation is the storage below that level.

4. Floods are routed through the spillway using HEC-1, modified Puls to determine the capability of the spillway.

- (1) U.S. Army Corps of Engineers, Hydrologic Engineering Center, Flood Hydrograph Package (HEC-1), Dam Safety Version, July 1978, Modification September 1978, Davis, California.
- (2) U.S. Department of the Interior, Bureau of Reclamation, Design of Small Dams, 1974, Washington, D.C.

**● ●**

283 3 10 0

193

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	52
--	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	----

**X 0 HEAD**

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100  
101  
102  
103  
104  
105  
106  
107  
108  
109  
110  
111  
112  
113  
114  
115  
116  
117  
118  
119  
120  
121  
122  
123  
124  
125  
126  
127  
128  
129  
130  
131  
132  
133  
134  
135  
136  
137  
138  
139  
140  
141  
142  
143  
144  
145  
146  
147  
148  
149  
150  
151  
152  
153  
154  
155  
156  
157  
158  
159  
160  
161  
162  
163  
164  
165  
166  
167  
168  
169  
170  
171  
172  
173  
174  
175  
176  
177  
178  
179  
180  
181  
182  
183  
184  
185  
186  
187  
188  
189  
190  
191  
192  
193  
194  
195  
196  
197  
198  
199  
200  
201  
202  
203  
204  
205  
206  
207  
208  
209  
210  
211  
212  
213  
214  
215  
216  
217  
218  
219  
220  
221  
222  
223  
224  
225  
226  
227  
228  
229  
230  
231  
232  
233  
234  
235  
236  
237  
238  
239  
240  
241  
242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281  
282  
283  
284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310  
311  
312  
313  
314  
315  
316  
317  
318  
319  
320  
321  
322  
323  
324  
325  
326  
327  
328  
329  
330  
331  
332  
333  
334  
335  
336  
337  
338  
339  
340  
341  
342  
343  
344  
345  
346  
347  
348  
349  
350  
351  
352  
353  
354  
355  
356  
357  
358  
359  
360  
361  
362  
363  
364  
365  
366  
367  
368  
369  
370  
371  
372  
373  
374  
375  
376  
377  
378  
379  
380  
381  
382  
383  
384  
385  
386  
387  
388  
389  
390  
391  
392  
393  
394  
395  
396  
397  
398  
399  
400  
401  
402  
403  
404  
405  
406  
407  
408  
409  
410  
411  
412  
413  
414  
415  
416  
417  
418  
419  
420  
421  
422  
423  
424  
425  
426  
427  
428  
429  
430  
431  
432  
433  
434  
435  
436  
437  
438  
439  
440  
441  
442  
443  
444  
445  
446  
447  
448  
449  
450  
451  
452  
453  
454  
455  
456  
457  
458  
459  
460  
461  
462  
463  
464  
465  
466  
467  
468  
469  
470  
471  
472  
473  
474  
475  
476  
477  
478  
479  
480  
481  
482  
483  
484  
485  
486  
487  
488  
489  
490  
491  
492  
493  
494  
495  
496  
497  
498  
499  
500  
501  
502  
503  
504  
505  
506  
507  
508  
509  
510  
511  
512  
513  
514  
515  
516  
517  
518  
519  
520  
521  
522  
523  
524  
525  
526  
527  
528  
529  
530  
531  
532  
533  
534  
535  
536  
537  
538  
539  
540  
541  
542  
543  
544  
545  
546  
547  
548  
549  
550  
551  
552  
553  
554  
555  
556  
557  
558  
559  
560  
561  
562  
563  
564  
565  
566  
567  
568  
569  
570  
571  
572  
573  
574  
575  
576  
577  
578  
579  
580  
581  
582  
583  
584  
585  
586  
587  
588  
589  
590  
591  
592  
593  
594  
595  
596  
597  
598  
599  
600  
601  
602  
603  
604  
605  
606  
607  
608  
609  
610  
611  
612  
613  
614  
615  
616  
617  
618  
619  
620  
621  
622  
623  
624  
625  
626  
627  
628  
629  
630  
631  
632  
633  
634  
635  
636  
637  
638  
639  
640  
641  
642  
643  
644  
645  
646  
647  
648  
649  
650  
651  
652  
653  
654  
655  
656  
657  
658  
659  
660  
661  
662  
663  
664  
665  
666  
667  
668  
669  
670  
671  
672  
673  
674  
675  
676  
677  
678  
679  
680  
681  
682  
683  
684  
685  
686  
687  
688  
689  
690  
691  
692  
693  
694  
695  
696  
697  
698  
699  
700  
701  
702  
703  
704  
705  
706  
707  
708  
709  
710  
711  
712  
713  
714  
715  
716  
717  
718  
719  
720  
721  
722  
723  
724  
725  
726  
727  
728  
729  
730  
731  
732  
733  
734  
735  
736  
737  
738  
739  
740  
741  
742  
743  
744  
745  
746  
747  
748  
749  
750  
751  
752  
753  
754  
755  
756  
757  
758  
759  
760  
761  
762  
763  
764  
765  
766  
767  
768  
769  
770  
771  
772  
773  
774  
775  
776  
777  
778  
779  
780  
781  
782  
783  
784  
785  
786  
787  
788  
789  
790  
791  
792  
793  
794  
795  
796  
797  
798  
799  
800  
801  
802  
803  
804  
805  
806  
807  
808  
809  
810  
811  
812  
813  
814  
815  
816  
817  
818  
819  
820  
821  
822  
823  
824  
825  
826  
827  
828  
829  
830  
831  
832  
833  
834  
835  
836  
837  
838  
839  
840  
84

**P 25.1 101. 120. 130. 140.**

—x

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100  
101  
102  
103  
104  
105  
106  
107  
108  
109  
110  
111  
112  
113  
114  
115  
116  
117  
118  
119  
120  
121  
122  
123  
124  
125  
126  
127  
128  
129  
130  
131  
132  
133  
134  
135  
136  
137  
138  
139  
140  
141  
142  
143  
144  
145  
146  
147  
148  
149  
150  
151  
152  
153  
154  
155  
156  
157  
158  
159  
160  
161  
162  
163  
164  
165  
166  
167  
168  
169  
170  
171  
172  
173  
174  
175  
176  
177  
178  
179  
180  
181  
182  
183  
184  
185  
186  
187  
188  
189  
190  
191  
192  
193  
194  
195  
196  
197  
198  
199  
200  
201  
202  
203  
204  
205  
206  
207  
208  
209  
210  
211  
212  
213  
214  
215  
216  
217  
218  
219  
220  
221  
222  
223  
224  
225  
226  
227  
228  
229  
230  
231  
232  
233  
234  
235  
236  
237  
238  
239  
240  
241  
242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281  
282  
283  
284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310  
311  
312  
313  
314  
315  
316  
317  
318  
319  
320  
321  
322  
323  
324  
325  
326  
327  
328  
329  
330  
331  
332  
333  
334  
335  
336  
337  
338  
339  
340  
341  
342  
343  
344  
345  
346  
347  
348  
349  
350  
351  
352  
353  
354  
355  
356  
357  
358  
359  
360  
361  
362  
363  
364  
365  
366  
367  
368  
369  
370  
371  
372  
373  
374  
375  
376  
377  
378  
379  
380  
381  
382  
383  
384  
385  
386  
387  
388  
389  
390  
391  
392  
393  
394  
395  
396  
397  
398  
399  
400  
401  
402  
403  
404  
405  
406  
407  
408  
409  
410  
411  
412  
413  
414  
415  
416  
417  
418  
419  
420  
421  
422  
423  
424  
425  
426  
427  
428  
429  
430  
431  
432  
433  
434  
435  
436  
437  
438  
439  
440  
441  
442  
443  
444  
445  
446  
447  
448  
449  
450  
451  
452  
453  
454  
455  
456  
457  
458  
459  
460  
461  
462  
463  
464  
465  
466  
467  
468  
469  
470  
471  
472  
473  
474  
475  
476  
477  
478  
479  
480  
481  
482  
483  
484  
485  
486  
487  
488  
489  
490  
491  
492  
493  
494  
495  
496  
497  
498  
499  
500  
501  
502  
503  
504  
505  
506  
507  
508  
509  
510  
511  
512  
513  
514  
515  
516  
517  
518  
519  
520  
521  
522  
523  
524  
525  
526  
527  
528  
529  
530  
531  
532  
533  
534  
535  
536  
537  
538  
539  
540  
541  
542  
543  
544  
545  
546  
547  
548  
549  
550  
551  
552  
553  
554  
555  
556  
557  
558  
559  
560  
561  
562  
563  
564  
565  
566  
567  
568  
569  
570  
571  
572  
573  
574  
575  
576  
577  
578  
579  
580  
581  
582  
583  
584  
585  
586  
587  
588  
589  
590  
591  
592  
593  
594  
595  
596  
597  
598  
599  
600  
601  
602  
603  
604  
605  
606  
607  
608  
609  
610  
611  
612  
613  
614  
615  
616  
617  
618  
619  
620  
621  
622  
623  
624  
625  
626  
627  
628  
629  
630  
631  
632  
633  
634  
635  
636  
637  
638  
639  
640  
641  
642  
643  
644  
645  
646  
647  
648  
649  
650  
651  
652  
653  
654  
655  
656  
657  
658  
659  
660  
661  
662  
663  
664  
665  
666  
667  
668  
669  
670  
671  
672  
673  
674  
675  
676  
677  
678  
679  
680  
681  
682  
683  
684  
685  
686  
687  
688  
689  
690  
691  
692  
693  
694  
695  
696  
697  
698  
699  
700  
701  
702  
703  
704  
705  
706  
707  
708  
709  
710  
711  
712  
713  
714  
715  
716  
717  
718  
719  
720  
721  
722  
723  
724  
725  
726  
727  
728  
729  
730  
731  
732  
733  
734  
735  
736  
737  
738  
739  
740  
741  
742  
743  
744  
745  
746  
747  
748  
749  
750  
751  
752  
753  
754  
755  
756  
757  
758  
759  
760  
761  
762  
763  
764  
765  
766  
767  
768  
769  
770  
771  
772  
773  
774  
775  
776  
777  
778  
779  
780  
781  
782  
783  
784  
785  
786  
787  
788  
789  
790  
791  
792  
793  
794  
795  
796  
797  
798  
799  
800  
801  
802  
803  
804  
805  
806  
807  
808  
809  
810  
811  
812  
813  
814  
815  
816  
817  
818  
819  
820  
821  
822  
823  
824  
825  
826  
827  
828  
829  
830  
831  
832  
833  
834  
835  
836  
837  
838  
839  
840  
84

—

—

Year	1950	1955	1960	1965	1970	1975	1980	1985	1990	1995	2000	2005	2010	2015	2020	2025	2030	2035	2040	2045	2050	2055	2060	2065	2070	2075	2080	2085	2090	2095	2100		
Population (millions)	1.5	1.6	1.7	1.8	1.9	2.0	2.1	2.2	2.3	2.4	2.5	2.6	2.7	2.8	2.9	3.0	3.1	3.2	3.3	3.4	3.5	3.6	3.7	3.8	3.9	4.0	4.1	4.2	4.3	4.4	4.5		
GDP (trillion USD)	0.5	0.6	0.7	0.8	0.9	1.0	1.1	1.2	1.3	1.4	1.5	1.6	1.7	1.8	1.9	2.0	2.1	2.2	2.3	2.4	2.5	2.6	2.7	2.8	2.9	3.0	3.1	3.2	3.3	3.4	3.5	3.6	
Life expectancy (years)	45	48	51	54	57	60	63	66	69	72	75	78	81	84	87	90	93	96	99	102	105	108	111	114	117	120	123	126	129	132	135	138	
Urban population (%)	20	25	30	35	40	45	50	55	60	65	70	75	80	85	90	95	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
Renewable energy (%)	10	15	20	25	30	35	40	45	50	55	60	65	70	75	80	85	90	95	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
CO2 emissions (Gt)	15	18	21	24	27	30	33	36	39	42	45	48	51	54	57	60	63	66	69	72	75	78	81	84	87	90	93	96	99	102	105	108	
Forest cover (%)	30	28	26	24	22	20	18	16	14	12	10	8	6	4	2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Water stress (%)	10	15	20	25	30	35	40	45	50	55	60	65	70	75	80	85	90	95	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
Healthcare spending (GDP %)	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	
Education spending (GDP %)	3	3.5	4	4.5	5	5.5	6	6.5	7	7.5	8	8.5	9	9.5	10	10.5	11	11.5	12	12.5	13	13.5	14	14.5	15	15.5	16	16.5	17	17.5	18	18.5	
Research & Development (GDP %)	1	1.5	2	2.5	3	3.5	4	4.5	5	5.5	6	6.5	7	7.5	8	8.5	9	9.5	10	10.5	11	11.5	12	12.5	13	13.5	14	14.5	15	15.5	16	16.5	
Unemployment (%)	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	
Income inequality (Gini index)	40	42	44	46	48	50	52	54	56	58	60	62	64	66	68	70	72	74	76	78	80	82	84	86	88	90	92	94	96	98	100	102	104
Gender inequality (GII)	0.7	0.75	0.8	0.85	0.9	0.95</																											

350. 195. 390. 7305.

27081

SD972.8

100

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS								
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	RATIO 8	RATIO 9
				.05	.10	.15	.20	.25	.30	.40	.50	1.00
HYDROGRAPH AT	HEAD	4.56 ( 11.81)	1	1224. ( 34.66)	2448. ( 69.31)	3672. ( 103.97)	4895. ( 138.62)	6119. ( 173.28)	7343. ( 207.94)	9791. ( 277.25)	12239. ( 346.56)	24477. ( 693.12)
	DAM	4.56 ( 11.81)	1	821. ( 23.25)	1723. ( 48.79)	2496. ( 70.69)	3437. ( 97.33)	4564. ( 129.23)	5769. ( 163.37)	8055. ( 228.10)	10526. ( 298.06)	22957. ( 650.06)

# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....

	ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM					
		965.00	965.00	972.80					
		0.	0.	390.					
		0.	0.	3547.					
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.05	966.24	0.00	126.	821.	0.00	41.17	0.00		
.10	970.22	0.00	210.	1723.	0.00	41.00	0.00		
.15	971.48	0.00	298.	2496.	0.00	41.17	0.00		
.20	972.68	0.00	382.	3437.	0.00	41.00	0.00		
.25	973.30	.50	457.	4564.	1.67	41.00	0.00		
.30	973.72	.92	515.	5769.	2.50	40.83	0.00		
.40	974.53	1.73	624.	8055.	3.50	40.83	0.00		
.50	975.23	2.43	719.	10526.	4.33	40.83	0.00		
1.00	977.37	4.57	1009.	22957.	6.67	40.67	0.00		